MYSORE HEADQUARTER RANGE.

Dated 3rd December 1918.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Headquarter Range, Mysore, up to the 28th December 1918, for constructing the following buildings as per plans and designs which may be seen at the office of the Assistant Engineer. The buildings must be completed by the end of June 1919.

Description.

(1) Constructing Servants' Quarters in the European Guests' Quarters at Mysore.
(2) Constructing quarters for the Mali and Sweeper in the above quarters.
(3) Constructing Store Room for the above quarters.

2. Tenders should be submitted on printed forms, which may be obtained from the Assistant Engineer and must be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The quantities noted are not guaranteed.

3. Tenders containing indefinite remarks against the rates for items such as "as per estimate," "as per market rates," etc., will not be considered. Specific rates for all items except lump sum ones must be entered in the tenders.

4. Each tender should be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for servants and Mali and a Store Room in the European Guests' Quarters at Mysore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender, or assign reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Assistant Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement of items of work with quantities for the respective buildings noted above :—

No.	Particulars	Per	Quantity
	Servants' Quarters.		
1	Earthwork excavation and filling in basement	C. yd.	78
2	Concrete foundation	C ft.	861
3	Filling in foundation and basement, with brick in chunam	"	1,685
4	Superstructure brick in mud	"	2,976
5	Burnt stone slabs 6" thick roughly dressed	S. ft.	478
6	Burnt stone pillars nicely dressed and grooves cut	"	104
7	Plastering with chunam	Sq.	60·99
8	White and colour washing	"	60·99
9	Teakwood work wrought and put up	C. ft.	130·98
10	Roofing with 1st Class Mangalore tiles on teak reepers complete	Sq.	21·67
11	Mangalore ridge tiles set in mortar	R. ft.	95
12	Teakwood battened doors complete	S. ft.	108
13	Do windows with iron bars complete	"	216
14	Do Cupboards with frames, shutters and cross planks, etc., complete	"	72
15	Do eave board	R. ft.	335
16	Flooring with Cudappa slabs over 3" concrete bed and cement pointing	Sq.	12·42
17	Silicate painting	"	9·00
18	Ventilating tiles	Each	12
19	Binding wall over gable	R. ft.	36
20	Wood oiling to wood work	L. S.	...
21	Constructing cisterns	Each	6
22	Do "V" shaped drain, with cement concrete and plasters	R. ft.	150
23	Clearing site and levelling ground	L. S.	...
	Mali and Sweepers' Quarters.		
1	Earthwork excavation and refilling	C. yd.	29
2	Filling foundation with concrete	C ft.	326
3	Burnt brick in mortar filling foundation and basement	"	637
4	Burnt brick in clay superstructure	"	985
5	Burnt stone slabs roughly dressed 6" thick	S. ft.	161
6	Do roughly dressed and grooves cut	"	40
7	Teakwood door battened with iron fittings, etc.	"	36
8	Do windows battened with iron bars and fittings, etc., complete	"	72
9	Do work wrought and put up	C. ft.	40·97
10	Roofing with 1st clas Mangalore tiles with reepers, etc., complete	Sq.	9·06
11	Ordinary ridge tiles set in mortar	R. ft.	35
12	Binding wall over the roof	"	42

No.	Particulars	Per	Quantity
13	Chunam plastering	Sq.	23
14	White washing	"	23
15	Flooring with Cudappa slabs over 3" concrete bed and cement pointing complete	"	4·21
16	Silicate painting to doors and windows	"	2·64
17	Wood oiling	L. S.	...
18	Earth forming and levelling	"	...
19	Teakwood cupboard with frame, shutters and cross planks	S. ft.	24
20	Ventilating tiles	Each	4
21	Constructing drains with cement, and concrete	L. S.	...
22	Teakwood eave board	R. ft.	154
23	Constructing cisterns	Each	2
	Store room.		
1	Earthwork excavation and refilling basement	C. yd.	19
2	Concrete filling for foundation	C. ft.	215
3	Burnt brick in mortar for foundation and basement	"	427
4	Burnt brick in clay superstructure	"	741
5	Burnt stone slabs roughly dressed 6" thick	S. ft.	109
6	Burnt stone pillars roughly dressed and grooved	"	32
7	Teakwood battened doors with iron fittings, etc, complete	"	24
8	Do windows with iron fittings including iron bars	"	48
9	Do work wrought and put up	"	31
10	Planking for wall shelves	"	18
11	Roofing with 1st class Mangalore tiles with reepers, etc., complete	Sqr.	6·20
12	Ordinary ridge tiles set in mortar	R. ft.	23
13	Chunam binding over roof	"	42
14	White washing	Sq.	15·34
15	Chunam plastering	"	15·34
16	Flooring with Cudappa slabs over 3" concrete bed and cement pointing, complete	"	2·75
17	Silicate painting to doors and windows	"	1·44
18	Wood oiling	L. S.	...
19	Earth forming and levelling	"	...
20	Teakwood eave board	R. ft.	12?

GURU RAO SIRSI,
Assistant Engineer.

HASSAN DIVISION.

Dated 29th November 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Hassan Division, up to 21st December 1918 for restoring Masavanghatta tank, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office Hassan between the hours of 11 A.M. to 5 P.M.

3. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Masavanghatta tank" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.